

Corrigendum - I

Tender No. WTL/DMB/NW/17-18/008 dated 14/06/2017

Sl. No.	Section	Clause No	Page No.	Present Entry	Replace with
1.	J		32	Minimum Specification of 22U Floor Mount RACK	Minimum Specification of 22U Floor Mount RACK, OEM shall have certifications e.g ISO 14001/ UL or other relevant certificates
2.	J		33	Minimum Specification of 9U Wall Mount RACK	Minimum Specification of 9U Wall Mount RACK, OEM shall have certifications e.g ISO 14001/ UL or other relevant certificates
3.	J		32	S. No. 10 Vertical Power Distribution Unit with 1x12nos. Of 5/15Amp round pin Indian style sockets	S. No. 10 Vertical Power Distribution Unit with 1x12nos. of 5/15Amp round pin Indian style sockets or 2x 6 nos. of 5/15Amp round pin Indian style sockets
4.	E	14	14	TIME SCHEDULE FOR DELIVERY & INSTALLATION The total delivery, installation & commissioning will have to be completed within 4-6 weeks from the date of Order.	TIME SCHEDULE FOR DELIVERY & INSTALLATION The total delivery, installation & commissioning at the Collectorate building and adjoining office buildings will have to be completed within 6-8 weeks from the date of Order. Implementation of campus area network at the distant offices e.g. Circuit house, DM Bungalow, ADM/ SDO bungalows will have to be completed within 10 weeks
5.	E	19	14/15	TERMS OF PAYMENT Payment terms will be on back-to-back basis, i.e., payment will be made only on receipt of payment from relevant customer, i.e., District Magistrate, Birbhum.	TERMS OF PAYMENT Payment terms will be on back-to-back basis, i.e., payment will be made only on receipt of payment from relevant customer, i.e., District Magistrate, Birbhum. 40% of materials cost shall be paid to the vendor on successful delivery of materials and submission of receipted challans duly signed by the customer. The balance payment will be released on completion of the project after submission of invoice along with installation and commissioning certificate, OTDR and penta scanner test reports signed by the end customer and all project documentations
6.	I		27/28	Sl. No. B1 Cat 6 UTP Cable Laying With PVC Casing & Conduit	Sl. No. B1 Cat 6 UTP Cable Laying With PVC Casing & Conduit with penta scanner testing
7.	I		27/28	Sl. No. B4 OFC Laying (Overhead) with stay wire & necessary accessories	Sl. No. B4 OFC Laying (Overhead) with stay wire & necessary accessories including OTDR testing

8.	I		27/28	Sl. No. B5 Laying of FO Cable (12/6 Core) with soft & hard Road cutting & digging & filling.& supplying of HDPE & GI & PVC Pipe	Sl. No. B5 Laying of FO Cable (24/12/6 Core) with soft & hard Road cutting ,digging , filling with supply of HDPE , GI & PVC Pipe including OTDR testing
9.	I		27/28	Sl. No. B6 OFC Laying within building with HDPE / PVC/Condiute pipe & proper casing as required	Sl. No. B6 OFC Laying within building with HDPE / PVC/Conduit pipe & proper casing as required including OTDR testing
10.	I		27/28	Sl. No. B7 OFC Laying through Micro tunneling including HDPE pipe and other accessories	Sl. No. B7 OFC Laying through Micro tunnelling including HDPE pipe and other accessories including OTDR testing
11.	BOQ has been revised. Revised BOQ uploaded.				